

CORRIGENDUM-1

“Supply, Installation, Testing, and Commissioning (SITC) of (120 HP) HVAC High Efficiency(VRV/VRF) type Air Conditioning system at Auditorium and Library Building, MDI Gurgaon”

With reference to the Tender published by MDI, Gurgaon on 15 January 2024, the following Corrigendum is issued.

Details	Old Description	Amended Description
PART-B, page no.28	Providing and laying of cable tray for exposed pipe. Size 300mm X 100mm	Providing and laying of cable tray for exposed pipe. Size 300mm X 100mm X 5 - 6 mm
SECTION-V GENERAL TERMS & CONDITIONS S.No.12, page.15	TERMS OF PAYMENT:- Subject to any deduction which the MDI may be authorized to make under this contract, the payment shall be made as follows “70% payment shall be made against the running bill on erection of material at site after deduction 5% security on adjustment of EMD.	TERMS OF PAYMENT:- 1. Subject to any deduction which the MDI may be authorized to make under this contract, the payment shall be made as follows: a. 70% payment against supply of Materials at MDI Gurgaon campus, as per the specification and quantity mentioned in the tender document BOQ (Pages No.27-30) and on submission of Proforma Invoice in original, Receipt voucher for the items supplied and certified to be in good and acceptable condition by the Estate deptt. b. 20% payment against the installation of complete work as per the specification of approved materials and scope of work, final Tax invoice, and certified measurement sheet by the estate deptt. for the items executed. c. 10% payment against Testing and Commissioning of complete work as per the specification of approved materials, and certified by the estate deptt. 2. Retention Amount:- Retention amount @5% of total invoice value/billed amount will be deducted from the bills and will be released after one year of date of handover of the completed work to MDI Gurgaon.
LOW SIDE WORK B , PIPING WORKS: Refrigerant Piping, page.28	Providing and fixing of refrigerant pipe with 13, 19 mm thick closed cell elastomeric nitrile rubber tabular insulation as per specifications and drawing (MAKES :- MANDEV, RAJCO , Maxflow DAIKIN - JOBU)	Providing and fixing of refrigerant pipe with 13, 19 mm thick closed cell elastomeric nitrile rubber tabular insulation as per specifications and drawing (MAKES :- MANDEV, RAJCO , Maxflow DAIKIN - JOBU)
1	34.1 mm 1.21 mm RM- 1580	1. 34.1 mm 1.21 mm RM- 158
2	28.5 mm 1.21 mm RM-1205	2. 28.5 mm 1.21 mm RM-120
3	22.2 mm 1.21 mm RM-987	3. 22.2 mm 1.21 mm RM-98.7
4	19.1 mm 1.00 mm RM-850	4. 19.1 mm 1.00 mm RM-85
5	15.9 mm 1.00 mm RM-755	5. 15.9 mm 1.00 mm RM-150
6	12.7 mm 0.80 mm RM-720	6. 12.7 mm 0.80 mm RM-72
7	9.5 mm 0.80 mm RM-465	7. 9.5 mm 0.80 mm RM- Rate Only
8	6.4 mm 0.80 mm RM-380	8. 6.4 mm 0.80 mm RM-Rate Only

2. The other terms and conditions mentioned in the Tender document will remain the same.